

- Roof truss
- LX bar
- Winch bar
- Fixed bar (ring beam)

Snape Maltings Concert Hall Lighting / Flying Bars

Drawing October 2008

Motor winch sets 1 to 4 have a working load of 400kg.


Hand winch sets 1 to 3 have a working load of 300kg

LX bars 1 to 5 have a working load of 540kg

All bars are 14m long

All flown pieces must have their weight clearly marked on them.

Bar measurements are taken from the front edge of the stage.



Scale Note. This drawing was prepared using TurboCad. When converted to DWG or DXF the units of measurement can get altered. The quantity will be correct, the type may be wrong! The drawing was done in metres, so if the scale seems wrong try altering the space unit to metres and check with the scale above.